



खुम्बु पासाङल्हामु गाउँपालिका

खुम्बु पासाङल्हामु गाउँपालिका

Khumbu Pasanglhamu Rural Municipality



गाउँ कार्यपालिकाको कार्यालय, चौरीखर्क, सोलुखुम्बु, कोशी प्रदेश, नेपाल
Office of the Rural Municipal Executive, Chaurikharka, Solukhumbu, Koshi Province, Nepal

प.सं. ०८१/०८२

च.नं. ६५४

मिति:-२०८१।०८।२४




विषय: दर भाउपत्र पेश गर्ने सम्बन्धमा ।

श्री

..... ।


खुम्बु पासाङल्हामु गाउँपालिका वडा नं .१ स्थित डिमदोर्जी शेर्पा पर्यटन सडकको विभिन्न स्थानमा वर्षायामको बाढीले सडकको सतह बगाई सवारी साधन आवत जावत गर्न कठिन भएकाले उक्त सडकको सतह मिलाई विभिन्न स्थानमा ढुङ्गा सोलिड गर्ने कार्यका लागि यस कार्यालयले तयार पारेको यसै पत्र साथ संलग्न बिल अफ क्वान्टिटीमा उल्लिखित आईटमका कार्यहरु के-कति दरमा गर्न सकिन्छ, ईच्छुक फर्म तथा कम्पनीहरुले ७ (सात) दिन भित्र यस कार्यालयमा आईपुग्ने गरी दरभाउ पत्र पेश गर्नु हुन अनुरोध छ ।


सुजन कुमार बुढाथोकी
प्रशासकीय अधिकृत

Khumbu Pasanglhamu Rural Municipality

Office of the Rural Municipal Executive
Chaurikharka, Solukhumbu

Bill of Quantity



[Handwritten Signature]

Name of Project: Road site clearance site drain and stone solling work

Location: Khumbu Pasang Rural Municipality-1, Solukhumbu

F/Y:2081/82

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	Roadway Excavation in all types of soil by mechanical means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer.	m ³	1938.90			
2	Roadway Excavation in ordinary rock by Mechanical Means : Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and lead as per Drawing and instruction of the Engineer.	m ³	27.33			
3	Dry Stone solling work in defferent chainage as per Drawing and instruction of the Engineer.	m ³	98.18			
Total amount						
VAT@13%						
Total Project Cost						

Total in words:

Name of firm

Address

Signature

Seal of Firm