



खुम्बु पासाङल्हामु गाउँपालिका
Khumbu Pasanglham Rural Municipality

गाउँ कार्यपालिकाको कार्यालय, चौम्वु, खुम्बु, कोशी प्रदेश, नेपाल
Office of the Rural Municipal Executive, Chaumvu, Solukhumbu, Koshi Province, Nepal



प.सं. ०८२/०८३

मिति: २०८२ १०५ १०४


च.नं. ८९

विषय: दर भाउपत्र पेश गर्ने सम्बन्धमा ।

श्री सबै निर्माण व्यवसायीहरु,

..... ।

खुम्बु पासाङल्हामु गाउँपालिकाभित्र रहेको झोलुङ्गे पुलहरुको मर्मत गर्ने कार्यको लागि यस कार्यालयले तयार पारेको यसै पत्र साथ संलग्न बिल अफ कान्टिटी (BOQ) मा उल्लेखित आईटमका कार्यहरु के-कति दरमा गर्न सकिन्छ, ईच्छुक फर्म तथा कम्पनीहरुले ७ (सात) दिन भित्र यस कार्यालयमा आईपुग्ने गरी दरभाउ पत्र पेश गर्नु हुन अनुरोध छ ।


सुजन कुमार बुढाथोकी
प्रशासकीय अधिकृत

Khumbu Pasanglhamu Rural Municipality
Office of the Rural Municipal Executive
Chaurikharka, Solukhumbu
Koshi Province, Nepal
Bill of Quantity



Name of Project: Maintenance of suspension bridge
Location: Khumbu Pasanglhamu R.M.

F/Y: 082/083

S.N.	Description of work	Unit	Estimated Quantity	Rate in (NRs) excluding VAT		Amount (NRs) excluding vat
				Rate in figure	Rate in words	
1	Clearance of bushes, grass, debris etc as per m2					
	Both side of bridge					
	Ward-1					
	khari khola-jaubari bridge	m ²	35.00			
	ward-2					
	Nabuk bridge	m ²	35.00			
	Hadikhola bridge	m ²	35.00			
	charikharka-tate bridge	m ²	35.00			
	Ward-3					
	Ghat - chharmading bridge	m ²	35.00			
	For Larchadobhan bridge	m ²	35.00			
	for Jorsalle bridge (dobhan side)	m ²	35.00			
	removing of khataa	m ²	4.00			
	for Jorsalle bridge (manjo side)	m ²	35.00			
	removing of khataa	m ²	4.00			
	for Benkar bridge	m ²	35.00			
	removing of khataa	m ²	4.00			
	for Phakding- Rangding bridge	m ²	35.00			
	removing of khataa	m ²	1.60			
	for Phakding-sanogumela bridge	m ²	35.00			
	for Thadokoshi bridge	m ²	35.00			
	Ward-4					



	for Phungithanga bridge	m ²	35.00			
	Pangboche-ABC bridge	m ²	35.00			
	Gabion wire mess netting-10 SWG					
2	(50x50 mesh size) as per m2					
	for Jorsalle bridge (dobhan side)	m ²	24.00			
	for Jorsalle bridge (manjo side)	m ²	291.84			
	for Benkar bridge	m ²	12.00			
		m ²	36.00			
	for Thadokoshi bridge	m ²	18.00			
	for Phungithanga bridge	m ²	252.00			
	for maintenace of Rest bridges	m ²	120.00			
	suspenders for replacing old					
3	broken suspenders of bridge					
	For Larchadobhan bridge	kg	22.32			
	for Jorsalle bridge (dobhan side)	kg	7.44			
	Phungithanga bridge	kg	7.44			
	for maintenace of Rest bridges	kg	37.20			
4	G1 walkway deck of bridge					
	for Jorsalle bridge (dobhan side)	kg	10.73			
	for Benkar bridge	kg	10.73			
	for Phakding- Rangding bridge	kg	16.09			
	for maintenace of Rest bridges	kg	134.10			
5	Hot deep galvanized bolts,Nuts & washers	kg	200.00			
6	Gabion wire 10 SWG heavy coatedfor binding of gabion side mess	kg	66.00			
7	Transportation of all materials for bridge maintenance to the all site					
	For ward-1 bridge	kg	85.85			
	For ward-2 bridges(hadikhola,nakchung,tate,sy angma,nabuk)	kg	107.26			



For ward-3 bridge	kg	1234.84			
For ward-4 bridge	kg	637.85			
Sub total					
VAT @ 13%					
Grand Total Amount					

Total in words:
 Name of firm
 Address
 Signature

Seal of Firm