

Office of the Rural Municipal Executive
 Chaurikharka, Solukhumbu
Bill of Quantity

Name of Project :Maintainance at Lukla Covered Hall

Site: Khumbu pasanglhamu R.M-02,Solukhumbu

F/Y: 2082/083



S.N	Description of work	t	Quantity	Rate in figure	Rate in Words	Amount
A. Civil Works						
1	Concrete works					
	M10 PCC of RCC work with cement sand and aggregate including mixing, curing and all completed work	Cum	1.00			
1.1	M20 PCC of RCC work with cement sand and aggregate including mixing, curing and all completed work	Cum	7.56			
2	Stone Soling Work		0.00			
2.1	150mm locally available stone soling with compaction and all completed work	Cum	1.80			
2	Formwork/Centering					
2.1	Formworks: Providing 12mm thick waterproof plywood and steel prop formwork for concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett including cost of all materials, all complete as per specification, drawings and instruction of engineer.	sqm	39.46			
	Woodwork					

S.N	Description of work	t	Quantity	Rate in figure	Rate in Words	Amount
	Supply and fixing of 38mm thick local wood panel wardrobe shutter including holdfast,kabja,chheskini,locking set and killa kanti and handle all complete as per instructipn of site engineer	sqm	4.38			
	Providing and fixing a 50 mm x 75 mm Local wood frame at 600 mm x 600 mm spacing, and covering it with 25 mm thick Sal wood planks.	sqm	28.80			
3	Reinforcement works					
3.1	Providing Reinforcement bars (Grade Fe 500 or above) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per design drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all RCC works including Formworks as per specification, drawing & instruction of site Engineer	kg	195.73			
4	Stone Masonry work					
4.1	Stone masonry work Above Ground Level in cement sand mortar (1:6)with locally available stone finished in perfect lines & level as per specification &, drawings all complete.	0	0.14			
6	Miscellaneous Work					

Site: Khumbu pasanglhamu R.M-02,Solukhumbu

S.N	Description of work	t	Quantity	Rate in figure	Rate in Words	Amount
6.1	Fe 250 Steel truss Work including cutting, welding, febricating and erection of all elements as per drawing specification	kg	775.84			
6.2	110mm upvc pipe NS 206/046-6kg/cm2 pressure	0	110.00			
6.3	UPVC Elbow 110 mm 90 degree bend	RM	20.00			
6.4	Transportation of UPVC pipe from ktm to Site	Kg	220.00			
Sub total						
VAT @ 13%						
Grand total						

Total in Words:

Name of Firm:

Address:

Signature:

Seal of Firm