



खुम्बु पासाङल्हामु गाउँपालिका
Khumbu Pasanglhamu Rural Municipality

गाउँ कार्यपालिकाको कार्यालय, चौरीखर्क, सोलुखुम्बु, कोशी प्रदेश, नेपाल
Office of the Rural Municipal Executive, Chaurikharka, Solukhumbu, Koshi Province, Nepal



प.सं. ०८२/०८३
च.नं. १४०७


मिति: २०८३ १०१ १०८


विषय: दर भाउपत्र पेश गर्ने सम्बन्धमा ।

श्री सबै निर्माण व्यवसायीहरु,

..... ।

खुम्बु पासाङल्हामु गाउँपालिका वडा नं ०५ कार्यालय मर्मत तथा व्यवस्थापन गर्ने कार्यको लागि यस कार्यालयले तयार पारेको यसै पत्र साथ संलग्न बिल अफ क्वान्टिटी (BOQ) मा उल्लेखित आईटमका कार्यहरु के-कति दरमा गर्न सकिन्छ, ईच्छुक फर्म तथा कम्पनीहरुले ७ (सात) दिन भित्र यस कार्यालयमा आईपुग्ने गरी दरभाउ पत्र पेश गर्नु हुन अनुरोध छ ।


सुबेन कुमार बुढाथोकी
प्रशासकीय अधिकृत



 Khumbu Pasanglhamu Rural Municipality

 Office of the Rural Municipal Executive

 Chaurikharka, Solukhumbu

 Bill of Quantity

[Handwritten Signature]

Name of the Project : Ward no 05 Karyalay marmat tatha bebasthapan

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Namche

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	The work of making a frame out of local wood and joining it is complete.	5.47	Cum			
2	Supplying and making work of 25 mm thick pine wood flake placed in a 50 mm x 75 mm pine frame on 600 mm x 600 mm.	19.23	sqm			
3	Supplying and fittings of Commercial Ply wood (12 mm)	5.76	Sqm			
4	Supplying and Laying of Carpet (durability through key metrics like fiber type (nylon/wool for durability), face weight (ideally 35+ oz for quality)	35.00	rm			
5	Supplying and Fittings of Plain glass 4 mm	2.47	Sq.m			
6	Supplying & Installing door panels by making a frame with 38 mm thick sawn pine wood	3.42	sqm			
7	Providing the materials and completing the roofing work with plain C.G.I. sheets (galvanized sheets) of 0.43 mm (26 gauge heavy) weighing 66 kg per bundle.	2.64	Sq.m			

Khumbu Pasanglhamu Rural Municipality
Office of the Rural Municipal Executive
Chaurikharka, Solukhumbu
Bill of Quantity



Name of the Project : Ward no 05 Karyalay marmat tatha bebasthapan

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Namche

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
8	Supplying and applying a GI plain sheet gutter 150 mm wide up to 450 mm and connect it to the rainwater pipe, including the work of fixing nuts, bolts, and washers.	43.00	rm			
9	Transportation and fittings of carpet	1.00	Ls			
Sub Total						
VAT@13%						
Grand Total						

Total in words:

Name of firm

Address

Signature

Seal of Firm