



ཨ། ཁུམ་བུ་པ་སངས་ལྷ་མ་གྱི་ཁུམ་བུ་གྲོང་ཁྱེད་

खुम्बु पासाङल्हामु गाउँपालिका

Khumbu Pasanglhamu Rural Municipality

गाउँ कार्यपालिकाको कार्यालय, चोरीखर्क, सोलुखुम्बु, कोशी प्रदेश, नेपाल
Office of the Rural Municipal Executive, Chaurikharka, Solukhumbu, Koshi Province, Nepal



प.सं.: २०८३/०८४

च.नं.: ४८३

मिति: २०८३/०६/२१

श्री सबै निर्माण व्यवसायीहरू,

बिषय:- दरभाउपत्र पेश गर्ने बारे।

यस गाउँपालिकाबाट चालु आ.व. २०८३।०८४ मा यसै पत्र साथ संलग्न BOQ मा उल्लिखित आइटमका कार्यहरू गर्नुपर्ने भएकाले उक्त कार्य त्यस फर्मबाट के, कति दर रेटमा उपलब्ध गराउन सकिन्छ? सात (७) दिन भित्र यस कार्यालयमा दर भाउपत्र पेश गर्नुहुन अनुरोध छ।

क्र.सं.	कामको विवरण	कार्यान्वयन हुने वडा	टोल	कैफियत
१.	डमातेड बस्ति: भित्रको बाटो स्तरोन्नति	३	डमातेड	

(सुजन कुमार बुढाथोकी)
अधिकृत (आठौं)

Bill of Quantity
FY:083/84

Project Name: डमतेड बस्ति: भिचको बाटो स्तरोन्नति

Location: Khumbu Pasanglhamu Rural Municipality-01, Solukhumbu

- A. The rate quoted here under shall be inclusive of:
1. Supplying the materials along with accessories to the site.
 2. Fixing and erecting them in position as per general practice, specifications and instructions of site Engineer
 3. Test & Maintenance up to the period, specified in the agreement
- B. The itemwise rate should be quoted without VAT

सुजात कार्वाङ (अतिरिक्त कार्य)
सुजात कार्वाङ (अतिरिक्त कार्य)
सुजात कार्वाङ (अतिरिक्त कार्य)

S.N.	Description	Unit	Quantity	In Figure	Rate excluding VAT		Total Amount
					In word		
1.0	Roadway Excavation in all types of soil by Manual Means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer.	Cu.m	262.50				
2.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cu.m	49.83				
3.0	Providing and laying of dry Stone Masonry Work as per Drawing and Technical Specifications.	cum	14.40				
4.0	Providing and laying of Plain Cement Concrete of manual mixed M 10 (or 1:3:6 one cement three sand and six crushed aggregate) in Foundation including compaction, curing, testing and relevant lead etc complete as per Drawing and Technical Specifications.	Cum	9.60				
	Sub-Total(B)						
	Total(A+B)						
	VAT(13%)						
	Grand Total						

Contractor's:
Name:
Sign:
Stamp:
Date: